

PARIVESH

(*Pro-Active and Responsive Facilitation by Interactive, and Virtuous Environmental Single-Window Hub*)

ENVIRONMENTAL
CLEARANCE



Government of India
Ministry of Environment, Forest and Climate Change
(Issued by the State Environment Impact Assessment
Authority(SEIAA), MAHARASHTRA)

To,

The -1

NILKANTH SUPERSTRUCTURES LLP

F-408, Tower - II, Seawoods Grand Central, Plot R-1, Sector 40, Nerul Node, Seawoods, Navi Mumbai. -400706

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC) in respect of project submitted to the SEIAA vide proposal number SIA/MH/INFRA2/423305/2023 dated 24 Mar 2023. The particulars of the environmental clearance granted to the project are as below.

1. EC Identification No.	EC23B038MH110322
2. File No.	SIA/MH/INFRA2/423305/2023
3. Project Type	New
4. Category	B
5. Project/Activity including Schedule No.	8(a) Building and Construction projects
6. Name of Project	Proposed residential cum commercial project located at plot bearing no.8A, Sector - 20, New Panvel, Navi Mumbai - 410206.
7. Name of Company/Organization	NILKANTH SUPERSTRUCTURES LLP
8. Location of Project	MAHARASHTRA
9. TOR Date	N/A

The project details along with terms and conditions are appended herewith from page no 2 onwards.

Date: 21/07/2023

(e-signed)
Pravin C. Darade , I.A.S.
Member Secretary
SEIAA - (MAHARASHTRA)



Note: A valid environmental clearance shall be one that has EC identification number & E-Sign generated from PARIVESH. Please quote identification number in all future correspondence.

This is a computer generated cover page.

STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/INFRA2/423305/2023
Environment & Climate Change
Department
Room No. 217, 2nd Floor,
Mantralaya, Mumbai- 400032.

To
M/s.Nilkanth Superstructures LLP,
Plot bearing no.8A, Sector – 20,
New Panvel, Navi Mumbai.

Subject : Environment Clearance for Proposed residential cum commercial project located at plot bearing no.8A, Sector – 20, New Panvel, Navi Mumbai by M/s.Nilkanth Superstructures LLP.

Reference : Application no. SIA/MH/INFRA2/423305/2023

This has reference to your communication on the above-mentioned subject. The proposal was considered by the SEAC-2 in its 203rd meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 261st (Day-1) meeting of State Level Environment Impact Assessment Authority (SEIAA) held on 09.06.2023.

2. Brief Information of the project submitted by you is as below:-

Sr. No.	Description	Details	
1	Proposal Number	SIA/MH/INFRA2/423305/2023	
2	Name of Project	Proposed residential cum commercial project located at plot bearing no.8A, Sector – 20, New Panvel, Navi Mumbai - 41020	
3	Project category	8 (a) B2	
4	Type of Institution	Private	
5	Project Proponent	Name	M/s. Nilkanth Superstructures LLP
		Regd. Office address	F408, Seawoods Grand Central, Seawoods, Navi Mumbai-400706
		Contact number	neelkanthdeepralty@gmail.com
		e-mail	9870488558
6	Consultant	Enviro Policy Research India Pvt. Ltd. Contact no.:9833825875 avick@eprindia.com ; avick1114@gmail.com QCI-NABET Accredited, Certificate No – NABET/EIA/2124/IA0076(Validity - 26.04.2024)	
7	Applied for	New	
8	Location of the project	Proposed residential cum commercial project located at plot bearing no.8A, Sector – 20, New Panvel, Navi Mumbai - 41020	
9	Latitude and Longitude	18°59'11.10"N 73° 7'20.29"E	
10	Plot Area (sq.m.)	5,064.350	
11	Deductions (sq.m.)	0	
12	Net Plot area (sq.m.)	5,064.350	
13	Ground coverage (m ²) & %	3216.761 sq. m & 63.517 %	

14	FSI Area (sq.m.)	19,586.746															
15	Non-FSI (sq.m.)	11,477.581															
16	Proposed built-up area (FSI + Non FSI) (sq.m.)	31,064.327															
17	TBUA (m ²) approved by Planning Authority till date	PMC file no.: BP - 16692															
18	Earlier EC details with Total Construction area, if any.	NA															
19	Construction completed as per earlier EC (FSI + Non FSI) (sq.m.)	NA															
20	Previous EC / Existing Building	Proposed Configuration	Reason for Modification / Change														
Building Name	Configuration	Height (m)		Building Name	Configuration	Height (m)											
Fresh Project			1 building with 3 wings (A-C)	2 No. of Basements +Ground floor + 1 st floor office and parking + 2 nd floor garden and flats + 3 rd to 13 th residential floors	42.25	-											
21	No. of Tenements & Shops	291 No. of flats; Commercial area: 1369.057 sq. m.															
22	Total Population	1361															
23	Total Water Requirements CMD	178.7 KLD															
24	Under Ground Tank (UGT) location	Basement															
25	Source of water	PMC															
26	STP Capacity & Technology	260 KLD capacity with MBBR Technology															
27	STP Location	Basement															
28	Sewage Generation CMD & % of sewage discharge in sewer line	148.7 KLD 58.6 KLD (32.8 %)															
29	Solid Waste Management during Construction Phase	<table border="1"> <thead> <tr> <th>Type</th><th>Quantity</th><th>Treatment / disposal</th></tr> </thead> <tbody> <tr> <td>Dry waste</td><td>5kg/day</td><td>Recycled, Handed over to local vendor</td></tr> <tr> <td>Wet waste</td><td>3.5 kg/day</td><td>Reuse, Use as compost for landscape</td></tr> <tr> <td>Construction waste</td><td>-</td><td>Handed over to local vendor</td></tr> </tbody> </table>	Type	Quantity	Treatment / disposal	Dry waste	5kg/day	Recycled, Handed over to local vendor	Wet waste	3.5 kg/day	Reuse, Use as compost for landscape	Construction waste	-	Handed over to local vendor			
Type	Quantity	Treatment / disposal															
Dry waste	5kg/day	Recycled, Handed over to local vendor															
Wet waste	3.5 kg/day	Reuse, Use as compost for landscape															
Construction waste	-	Handed over to local vendor															
30	Total Solid Waste Quantities with typeduring Operation Phase & Capacity of OWC to be installed	<table border="1"> <thead> <tr> <th>Type</th><th>Quantity (Kg/d)</th><th>Treatment / disposal</th></tr> </thead> <tbody> <tr> <td>Dry waste</td><td>375.4 kg/day</td><td>Recycle, Handed over to local vendor</td></tr> <tr> <td>Wet waste</td><td>250.3 kg/day</td><td>Reuse, Use as compost for landscape</td></tr> <tr> <td>E-Waste</td><td>-</td><td>Recycle, Handed over to local vendor</td></tr> <tr> <td>STP Sludge (dry)</td><td>-</td><td>Reuse, Use as compost for landscape</td></tr> </tbody> </table>	Type	Quantity (Kg/d)	Treatment / disposal	Dry waste	375.4 kg/day	Recycle, Handed over to local vendor	Wet waste	250.3 kg/day	Reuse, Use as compost for landscape	E-Waste	-	Recycle, Handed over to local vendor	STP Sludge (dry)	-	Reuse, Use as compost for landscape
Type	Quantity (Kg/d)	Treatment / disposal															
Dry waste	375.4 kg/day	Recycle, Handed over to local vendor															
Wet waste	250.3 kg/day	Reuse, Use as compost for landscape															
E-Waste	-	Recycle, Handed over to local vendor															
STP Sludge (dry)	-	Reuse, Use as compost for landscape															

31	R.G. Area in sq.m.	RG required – 506.435 Sq. m.						
		RG provided on Mother earth- 541.752 sq. m.						
		RG on Podium – 1077.934 sq. m.						
		Total RG proposed– 1619.686 sq. m.						
		Existing trees on plot: 0 nos.						
		Total number of trees to be planted: Nos. 199 Nos.						
		a) In RG area: (including periphery plantation) on ground: 63 Nos.						
		b) In Miyawaki Plantation (out of total no of plantation):0Nos.						
		Number of trees to be cut: 0						
		Number of trees to be transplanted:0						
32	Power requirement	<p>During Operation Phase:</p> <table border="1"> <tr> <td>Details</td> <td></td> </tr> <tr> <td>Connected load (kW)</td> <td>2131</td> </tr> <tr> <td>Demand load (kW)</td> <td>925</td> </tr> </table>	Details		Connected load (kW)	2131	Demand load (kW)	925
Details								
Connected load (kW)	2131							
Demand load (kW)	925							
33	Energy Efficiency	<p>a) Total Energy saving (%): 20%</p> <p>b) Solar energy (%): 5%</p>						
34	D.G. set capacity	1*380 kVA						
35	No. of 4-W & 2-W Parking with 25% EV	<p>Total 4- Parking Provided: 254 nos.</p> <p>Total 2- wheeler proposed: 105 nos.</p> <p>Electrical Charging Points Proposed: 97 nos.</p> <p>% of Charging points: 38.18%</p>						
36	No. & capacity of Rain water harvesting tanks /Pits	RWH Tank1 and 2: 75 KLD each						
37	Project Cost in (Cr.)	161.30 Cr.						
38	EMP Cost	<p>During Construction Phase: 29.75 lakhs</p> <p>During Operation Phase: and OM Cost: 237.86 lakhs</p> <p>and OM 18.59 Lakhs</p>						
39	CER Details with justification if any....as per MoEF&CC circular dated 01/05/2018	<p>Not applicable</p> <p>(as per MoEF&CC OM F. NO. 22-65/2017-IA.III dt. 30.09.2020)</p>						
40	Details of Court Cases/litigations w.r.t the project and project location, if any.	No						

3. The proposal has been considered by SEIAA in its 260th (Day-1) meeting held on 09.06.2023 and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

Specific Conditions:

A. SEAC Conditions-

1. PP to submit IOD/IOA/Concession Document/Plan Approval or any other form of documents as applicable clarifying its conformity with local planning rules and provisions as per the Circular dated 30.01.2014 issued by the Environment Department, Govt. of Maharashtra.
2. PP to obtain following NOCs & remarks:

- a)Sewer Connection; c) Storm Water Drain remarks/NOC; f) SWM/C&D NOC.
- 3. PP to relocate parking proposed near to STP & DG set.
- 4. PP to provide turning radius of 9.0 Mtr for proper movement of Fire Tender & submit revised fire tender movement plan.
- 5. PP to submit section of STP through ramp.
- 6. PP to explore more energy savings in the project.
- 7. PP to count trees planted on ground only for calculation of nos. of trees to be planted as per norms.
- 8. PP to submit cross section of roads at four places showing clear road width, side margins provided from building line/compound wall etc. for services like drainage lines, plantation, parking etc.

B. SEIAA Conditions

- 1. PP has proposed mandatory RG of 541.752 m² on ground. Local planning authority to ensure compliance of the same.
- 2. PP to keep open space unpaved so as to ensure permeability of water. However, whenever paving is deemed necessary, PP to provide grass pavers of suitable types & strength to increase the water permeable area as well as to allow effective fire tender movement.
- 3. PP to achieve at least 5% of total energy requirement from solar/other renewable sources.
- 4. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
- 5. SEIAA after deliberation decided to grant EC for – FSI- 19586.746 m², Non FSI- 11477.581 m², Total BUA- 31064.327 m². (Plan approval No- PMC/TP/N.Panvel/20/8A/21-23/16625/1333/2023 dated on 8.6.2023)

General Conditions:

a) Construction Phase :-

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.
- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation

with Ground Water Authority.

- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
- IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- X. The Energy Conservation Building code shall be strictly adhered to.
- XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas) Protection and Preservation of Trees Act, 1975 as amended during the validity of Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
- XVII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- XVIII. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
- XIX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

B) Operation phase:-

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an

independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.

- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
- XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at parivesh.nic.in
- XII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
- XIII. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO₂, NO_x (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

C) General EC Conditions:-

- I. PP has to strictly abide by the conditions stipulated by SEAC& SEIAA.
- II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
- V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
- VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.

4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.

5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.

6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.

7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.

8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the

Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.

9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.



Pravin Darade
(Member Secretary, SEIAA)

Copy to:

1. Chairman, SEIAA, Mumbai.
2. Secretary, MoEF & CC, IA- Division MOEF & CC
3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
4. Regional Office MoEF & CC, Nagpur
5. District Collector, Raigad.
6. Commissioner, Panvel Municipal Corporation
7. Regional Officer, Maharashtra Pollution Control Board, Navi Mumbai.